

### FOUNDATION PLAN

SCALE : 1/4" = 1'-0"

### FOUNDATION NOTES:

- ALL DIMENSIONS SHALL BE VERIFIED WITH THE ARCHITECT'S DRAWINGS ANY DISCREPANCIES SHALL BE RESOLVED PRIOR TO COMMENCING OF WORK.
- D.F.P.I. PLATE TO BE SECURED WITH 1/2" DIAMETER BY 10' LONG ANCHOR BOLTS WITH A STANDARD CUT WASHER EMBEDDED AT LEAST 7" INTO CONCRETE WITH A MAXIMUM SPACING OF 72" O.C. THERE SHALL BE A MINIMUM OF TWO BOLTS PER PIECE OF FOUNDATION PLATE WITH ONE BOLT LOCATED WITHIN 12" MAX. & 4-1/2" MIN. OF EA. END OF EA. PIECE. **AT SHEAR WALLS** A PROPERLY SIZED NUT AND 3"x3"x.225" THICK WASHER SHALL BE TIGHTENED ON EA. BOLT TO THE PLATE. HOLE IN PLATE WASHER CAN BE DIAGONALLY SLOTTED W/ A WIDTH OF UP TO 3/16" LARGER THAN BOLT DIAMETER & A SLOT LENGTH NOT TO EXCEED 1 3/4", PROVIDED A STANDARD CUT WASHER IS PLACED BETWEEN THE PLATE WASHER & THE NUT. U.N.O. BY SUB LETTER 'C' WHEN A CUT WASHER IS OKAY.
  - ALL INTERIOR NON-SHEAR WALLS ARE TO BE SECURED WITH SHOT PINS INSTALLED PER MANUFACTURERS RECOMMENDATIONS, U.N.O. STRUCTURAL ENGINEERS CALCULATIONS GOVERN IN ALL CASES.
  - INSTALL ALL SIMPSON (OR APPROVED EQUAL) FOUNDATION HARDWARE PER MANUFACTURERS RECOMMENDATIONS. DEEPEN FOOTING WHERE NECESSARY TO PROVIDE ANCHOR EMBEDMENT AT HOLDOWN LOCATIONS.

### NOTE:

WHEN REQUIRED BY LOCAL BUILDING DEPARTMENT ALL ANCHOR BOLTS AND HOLDOWN BOLTS TO BE SET IN PLACE PRIOR TO CITY FOUNDATION INSPECTION

### SOIL INFORMATION:

- FOUNDATION SIZES, DEPTHS, AND REINFORCEMENT ARE AS RECOMMENDED WITHIN THE OWNER/DEVELOPER'S SOILS ENGINEERS REPORT. SOILS ENGINEER TO PROVIDE FOUNDATION INSPECTION AS OUTLINED IN LATEST SOIL REPORT.
- OWNER/DEVELOPER AND SUBCONTRACTORS ARE TO REVIEW THE SOILS REPORT PRIOR TO COMMENCING CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE OWNER, DEVELOPER AND SUBCONTRACTOR TO VERIFY THAT THE REPORT IS CURRENT AND PLAN REQUIREMENTS ARE CONSISTENT WITH ANY UPDATED SOIL REPORTS. ES/FME IS TO BE SUPPLIED WITH ALL UPDATED REPORTS.

### ANCHOR BOLT LEGEND:

- AB32 : 1/2" DIA. X 10' ANCHOR BOLTS AT 32" O.C.
- AB24 : 1/2" DIA. X 10' ANCHOR BOLTS AT 24" O.C.
- AB2 : 1/2" DIA. X 10' ANCHOR BOLTS AT # O.C.
- 2AB : (2) 1/2" DIA X 10' ANCHOR BOLTS.
- 3AB : (3) 1/2" DIA X 10' ANCHOR BOLTS.
- #AB : (#) 1/2" DIA X 10' ANCHOR BOLTS.
- #ABC : C DENOTES STANDARD CUT WASHERS OKAY IN LIEU OF 3" SQ. ONLY REQUIRED.
- 2-#4 : PROVIDE A TOTAL OF 2 #4 AT TOP AND 2 #4 AT BOTTOM OF FOOTING, 4' PAST POSTS.
- 3-#4 : PROVIDE A TOTAL OF 3 #4 AT TOP AND 3 #4 AT BOTTOM OF FOOTING, 4' PAST POSTS.
- 2-#5 : PROVIDE A TOTAL OF 2-#5 AT TOP AND 2-#5 AT BOTTOM OF FOOTING, 6' PAST POSTS.
- HDU2 : (1) SIMPSON HDU# PER POST.
- HDU# : (1) SIMPSON HDU# PER POST.
- HT4 : (1) SIMPSON HT4 PER POST.
- HT5 : (1) SIMPSON HT5 PER POST.
- PHD6 : (1) SIMPSON PHD6 PER POST.
- HD8A : (1) SIMPSON HD8A PER POST.
- HD10A : (1) SIMPSON HD10A PER POST.
- HD14A : (1) SIMPSON HD14A PER POST.
- HD08 : (1) SIMPSON HD08-SDS3 PER POST.
- HHQ11 : (1) SIMPSON HHQ11-SDS2.5 PER POST.
- HHQ14 : (1) SIMPSON HHQ14-SDS2.5 PER POST.

REFER TO ARCHITECTURAL PLANS FOR ALL DIMENSIONS

\* ALT. TO 1/2" ANCHOR BOLTS SIMPSON MASA AT A 1-1 RATIO

ALL GRADE BEAMS 8"x22 1/2" THICK W/ 2-#5 TOP & BOTTOM, U.N.O. W/ #3 TIES @ 12" O.C., U.N.O.

ALL PIERS TYPE [A] UNLESS NOTED OTHERWISE (U.N.O.)

PIER SCHEDULE	SEE (31) SD2 FOR TYP. CONN.		
TYPE	DEPTH INTO BEDROCK	CAPACITY	VERT. REINF.
A	5'-0"	11,715 *	(5) #6
B	8'-0"	18,840 *	(4) #6

- ALL PIERS TO BE INTERCONNECTED WITH GRADE BEAMS

PIERS:  
 16" # PIER W/ #3 TIES AT 12" O.C. PIERS SHALL PENETRATE AT LEAST 5'-0" INTO BEDROCK 4' A MIN. OF 6" BELOW THE LOWEST ADJACENT GRADE AS IDENTIFIED BY THE SOILS ENGINEER DURING CONSTRUCTION (SEE SOILS REPORT FOR MORE RECOMMENDATIONS).  
 THE EXCAVATION OF ALL DRILLED SHAFTS SHOULD BE OBSERVED BY A CORNERSTONE REPRESENTATIVE TO CONFIRM THE SOIL PROFILE. VERIFY THAT THE PIERS EXTEND THE MINIMUM DEPTH INTO SUITABLE MATERIALS AND THAT THE PIERS ARE CONSTRUCTED IN ACCORDANCE WITH OUR RECOMMENDATIONS AND PROJECT REQUIREMENTS. THE DRILLED SHAFTS SHOULD BE STRAIGHT, DRY, AND RELATIVELY FREE OF LOOSE MATERIAL BEFORE REINFORCING STEEL IS INSTALLED AND CONCRETE IS PLACED. IF GROUND WATER CANNOT BE REMOVED FROM THE EXCAVATIONS PRIOR TO CONCRETE PLACEMENT, DRILLING SLURRY OR CASING MAY BE REQUIRED TO STABILIZE THE SHAFT AND THE CONCRETE SHOULD BE PLACED USING A TREMIE PIPE, KEEPING THE TREMIE PIPE BELOW THE SURFACE OF THE CONCRETE TO AVOID ENTRAPMENT OF WATER OR DRILLING SLURRY IN THE CONCRETE.

INDICATES 24" CAISSONS W/ 10-#6 VERT. BARS MIN. 13' INTO BEDROCK.

INDICATES RETAINING WALL

REVISIONS

ES/FME, INC.  
 STRUCTURAL ENGINEERS  
 SAN ANTONIO, TX 78205  
 SAN FRANCISCO, CA 94107  
 PHOENIX, AZ 85001  
 P.O. BOX 1000  
 SAN ANTONIO, TX 78205

FOUNDATION PLAN  
 LOT 10

" HIGHLAND ESTATES "  
 SAN MATEO COUNTY, CA.  
 THE CHAMBERLAIN GROUP  
 MGA



DRAWN  
 CHECKED  
 PLOT DATE  
 12/01/2016  
 JOB NO.  
 C169  
 SHEET

S10-1

SHEET: 2 OF: 7



**LATERAL SHEAR NOTES:**

- (2013 CBC, S0PWS-2008; SEISMIC DESIGN CATEGORY D & E) FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16' O.C.
- VERTICAL:**
- 10. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 6" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 260 PLF
  - 11. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 4" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 350 PLF
  - 12. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 3" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 490 PLF
  - 13. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 640 PLF
  - 14. 1/2" (OR 15/32) WOOD STRUCTURAL PANEL WITH 104 COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 770 PLF
  - 15. 1/2" (OR 15/32) STRUCT. I WOOD PANEL WITH 104 COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 870 PLF

- HORIZONTAL:** (3/8" PANEL VALUES AND NAILING BELOW MAY BE USED FOR 15/32" PANELS)
- 20. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 240 PLF
  - 21. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 PLF
  - 22. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 480 PLF
  - 23. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 2.5" O.C. STAGE. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 545 PLF
  - 24. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 PLF
  - 25. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 425 PLF
  - 26. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 2.5" O.C. STAGE. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 640 PLF
  - 27. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 2" O.C. STAGE. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 730 PLF

**NOTES:**

- A. WOOD STRUCTURAL PANEL: MATERIAL APPROVED BY APA, PFS/TECO OR PITTSBURGH TESTING LABORATORIES THESE VALUES ARE FOR DOUG-FIR LARCH OR SOUTHERN PINE, OTHER LUMBER SPECIES MAY DIFFER IN SHEAR CAPACITIES.
- B. PROVIDE 2x BLOCKING AT HORIZONTAL WOOD STRUCTURAL PANEL JOINTS.
- C. WHERE WOOD STRUCTURAL PANEL IS APPLIED ON BOTH FACES OF WALL AND NAIL SPACING IS LESS THAN 6" O.C. PANEL JOINTS SHALL BE OFFSET TO FAIL ON DIFFERENT FRAMING MEMBERS OR FRAMING SHALL BE 3x OR WIDER AND NAILS STAGGERED ON EACH SIDE.
- D. FOR SHEAR WALLS USE THE FOLLOWING:
  - 1) USE 3x MEMBER @ PANEL JOINTS & HORIZONTAL BLOCKING
  - 2) EDGE NAILING SHALL BE STAGGERED
  - 3) 104 SHORT BOX NAILS MAY BE USED IN LIEU OF 84 COMMON NAILS @ SHEAR WALLS ONLY. REQUIRED PLATE WASHERS AT SHEAR WALLS TO BE 3" x 3" x 22# STEEL PLATE.
- E. U.N.G. WITH SUB SCRIPIT c WHERE STANDARD CUT WASHERS ARE O.KAY (S0PWS SECT. 4.3.6.4.3) WASHER MAY BE SLOTT PROVIDED A STANDARD CUT WASHER IS PROVIDED BETWEEN THE WASHER AND NUT. WASHER TO BE INSTALLED WITHIN 1/2" OF SHEATHED SIDE OF PLATE
- G. A STANDARD CUT WASHER MAY BE USED AT ALL NON-SHEAR WALL LOCATIONS WITH ANCHOR BOLTS.

**HORIZONTAL:**  
ALL ROOF AND FLOOR SHEATHING TO BE EXPOSURE 1 OR EXTERIOR (TABLE 2306.2.1)

**ROOF:**  
JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL PH 32/16, WITH 80% AT 6" O.C. EDGES AND BOUNDARIES, 12" O.C. FIELD

**FLOOR:**  
HORIZONTAL DIAPHRAGM VALUES FOR 3/8" WOOD STRUCTURAL PANELS MAY BE USED FOR 15/32" WOOD STRUCTURAL PANELS, U.N.G.  
+ JOIST SPACING EQUAL TO OR LESS THAN 16" O.C. 19/32" WOOD STRUCTURAL PANEL T&G SHG, PH 32/16, w/109% AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.  
JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL T&G SHG, PH 40/20, w/109% AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.  
JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 23/32" WOOD STRUCTURAL PANEL T&G SHG, PH 48/24, w/109% AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.  
+ PANEL EDGES SHALL HAVE APPROVED T&G JOINTS OR SHALL BE SUPPORTED WITH BLOCKING NOT REQUIRED WHEN LIGHTWEIGHT CONCRETE IS PLACED OVER SUBFLOOR.

**FRAMING LEGEND:**

INDICATES SPAN AND DIRECTION OF ROOF JOISTS AND RAFTERS

INDICATES SPAN AND DIRECTION OF TRUSSES

INDICATES SPAN AND DIRECTION OF FLOOR JOISTS

INDICATES SPAN AND DIRECTION OF CEILING JOISTS

INDICATES SPAN AND DIRECTION OF DECK JOISTS (SLOPED AS REQUIRED)

MARK	SPACING	MANUFACTURER	OPTIONS
C	1-JOIST @ 12" O.C.	0	11 7/8" MULL
R	1-JOIST @ 16" O.C.	0	-
S	1-JOIST @ 18" O.C.	0	-
G	2X10 AT 12" O.C.	0	-
H	2X10 AT 16" O.C.	0	11 7/8" TJI / 360
K	2X10 AT 24" O.C.	0	-
L	2X12 AT 16" O.C.	0	-
M	2X12 AT 18" O.C.	0	11 7/8" TJI / 235
N	2X12 AT 24" O.C.	0	-
P	2X12 AT 16" O.C.	0	-
T	TRUSS AT 24" O.C.	2	19.2" O.C. / 3

INDICATES (1) 1 3/4" x DEPTH OF JOIST MICROLAM LVL 1.9 E

PSL INDICATES PARALLEL PSL 2.0 E

TSR INDICATES 1 1/2" BY DEPTH OF JOIST TIMBERSTRAND RIM

E.N. INDICATES EDGE NAILING @ 6" O.C.

G.T. GIRDER TRUSS


C-TM INDICATES CONNECTION BY TRUSS MANUFACTURER

INDICATES INTERIOR BEARING WALL

INDICATES INTERIOR BEARING WALL

NOTE: APPLY SHEAR PRIOR TO FRAMING OF PERPENDICULAR WALL AND/OR BOX-OUTS. (WHERE APPLICABLE)


FRAMING NOTES LEGEND	CEILING JOIST SCHEDULE
MARK: DESCRIPTION	SIZE SPACING SPAN GRADE NO 2
SPR1Z: 164 SOLE PLATE NAILING @ 12" O.C.	2x4 12" O.C. 2-1"
SPR10: 164 SOLE PLATE NAILING @ 10" O.C.	2x4 10" O.C. 2-2"
SPR8: 164 SOLE PLATE NAILING @ 8" O.C.	2x4 8" O.C. 2-2"
SPR6: 164 SOLE PLATE NAILING @ 6" O.C.	2x4 6" O.C. 2-2"
SPR4: 164 SOLE PLATE NAILING @ 4" O.C.	2x4 4" O.C. 2-2"
SPR3: 164 SOLE PLATE NAILING @ 3" O.C.	2x4 3" O.C. 2-2"
SPR2: 164 SOLE PLATE NAILING @ 2" O.C.	2x4 2" O.C. 2-2"



**FOUNDATION & FIRST FLOOR  
FRAMING PLAN**

SCALE: 1/4" = 1'-0"

REFER TO SHEET S10-1  
FOR NOTES ON DRILLED  
PIERS.



**LATERAL SHEAR NOTES:**

- ( 2013 CBC, SDPWS-2008 ; SEISMIC DESIGN CATEGORY D & E ) FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16' O.C.
- TABLE 4.3A, AFPA SDPWS-2008
- 10. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 6" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 260 PLF
  - 11. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 4" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 350 PLF
  - 12. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 3" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 490 PLF
  - 13. 3/8" WOOD STRUCTURAL PANEL WITH 8d COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 640 PLF
  - 14. 1/2" (OR 15/32) WOOD STRUCTURAL PANEL WITH 10d COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 770 PLF
  - 15. 1/2" (OR 15/32) STRUCT. I WOOD PANEL WITH 10d COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 870 PLF
- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 24" O.C.
- 20. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 240 PLF
  - 21. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 PLF
  - 22. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 480 PLF
  - 23. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 8d COMMON NAILS AT 2" O.C. STAGE. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 545 PLF
- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16' O.C.
- 24. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 6" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 PLF
  - 25. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 4" O.C. STAGE. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 425 PLF
  - 26. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 2" O.C. STAGE. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 640 PLF
  - 27. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 10d COMMON NAILS AT 2" O.C. STAGE. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 730 PLF

NOTES:

- A. WOOD STRUCTURAL PANEL: MATERIAL APPROVED BY APA, PFS/TECO OR PITTSBURGH TESTING LABORATORIES THESE VALUES ARE FOR DOUG-FIR LARCH OR SOUTHERN PINE, OTHER LUMBER SPECIES MAY DIFFER IN SHEAR CAPACITIES.
- B. PROVIDE 2x BLOCKING AT HORIZONTAL WOOD STRUCTURAL PANEL JOINTS.
- C. WHERE WOOD STRUCTURAL PANEL IS APPLIED ON BOTH FACES OF WALL AND NAIL SPACING IS LESS THAN 6" O.C. PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS OR FRAMING SHALL BE 3x OR WIDER AND NAILS STAGGERED ON EACH SIDE.
- D. FOR SHEAR WALLS USE THE FOLLOWING:
  - 1) USE 3x MEMBER @ PANEL JOINTS & HORIZONTAL BLOCKING
  - 2) EDGE NAILING SHALL BE STAGGERED
  - 3) 10d SHORT BOX NAILS MAY BE USED IN LIEU OF 8d COMMON NAILS @ SHEAR WALLS ONLY. REQUIRED PLATE WASHERS AT SHEAR WALLS TO BE 3" x 3" x 23G STEEL PLATE. U.N.G. WITH SUB SCRIPIT c. WHERE STANDARD CUT WASHERS ARE OKAY (SDPWS SECT. 4.3.6.4.3) WASHER MAY BE SLOT OUT PROVIDED A STANDARD CUT WASHER IS PROVIDED BETWEEN THE WASHER AND NUT. WASHER TO BE INSTALLED WITHIN 1/2" OF SHEATHED SIDE OF PLATE.
  - 4) A STANDARD CUT WASHER MAY BE USED AT ALL NON-SHEAR WALL LOCATIONS WITH ANCHOR BOLTS.


ALL ROOF AND FLOOR SHEATHING TO BE EXPOSURE 1 OR EXTERIOR (TABLE 2306.2.1)

ROOF: JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL PI 32/16, WITH 8d AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD. HORIZONTAL DIAPHRAGM VALUES FOR 3/8" WOOD STRUCTURAL PANELS MAY BE USED FOR 15/32" WOOD STRUCTURAL PANELS, U.N.G.

FLOOR: JOIST SPACING EQUAL TO OR LESS THAN 16" O.C. 19/32" WOOD STRUCTURAL PANEL TAG SHG, PI 32/16, w/10d's AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD. JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL TAG SHG, PI 40/20, w/10d's AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD. JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 23/32" WOOD STRUCTURAL PANEL TAG SHG, PI 48/24, w/10d's AT 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.

- PANEL EDGES SHALL HAVE APPROVED TAG JOINTS OR SHALL BE SUPPORTED WITH BLOCKING NOT REQUIRED WHEN LIGHTWEIGHT CONCRETE IS PLACED OVER SUBFLOOR.

**FRAMING LEGEND:**



MARK	DESCRIPTION	CEILING JOIST SCHEDULE
SPR1Z	16d SOLE PLATE NAILING @ 12" O.C.	2x4 12" O.C. 8'-1"
SPR10	16d SOLE PLATE NAILING @ 10" O.C.	2x4 10" O.C. 7'-2"
SPR8	16d SOLE PLATE NAILING @ 8" O.C.	2x4 8" O.C. 6'-3"
SPR6	16d SOLE PLATE NAILING @ 6" O.C.	2x4 6" O.C. 5'-4"
SPR4	16d SOLE PLATE NAILING @ 4" O.C.	2x4 4" O.C. 4'-5"
SPR2	16d SOLE PLATE NAILING @ 2" O.C.	2x4 2" O.C. 3'-6"
SD33	1 1/2" x 4" 17G SPS SHEATH @ 3" O.C.	2x4 2" O.C. 18'-1"

**SECOND FLOOR FRAMING PLAN**  
SCALE : 1/4" = 1'-0"

REVISIONS



**ESI/FME, INC.**  
STRUCTURAL ENGINEERS  
1000 CALIFORNIA STREET  
SAN ANTONIO, TX 78205  
PHONE: 781-835-2800  
FAX: 781-835-2819  
LIC#0088 02/07/2016

**SECOND FLOOR FRAMING PLAN**  
**LOT 10**

**"HIGHLAND ESTATES"**  
SAN MATEO COUNTY, CA.  
THE CHAMBERLAIN GROUP  
MGA

PROFESSIONAL ENGINEER  
D. L. COREY  
C 35407  
CIVIL  
STATE OF CALIFORNIA

DRAWN -  
CHECKED -  
PLOT DATE 12/01/2016  
JOB NO. C169  
SHEET  
**S10-3**  
SHEET: 4 OF: 7



**ROOF FRAMING PLAN**


SCALE : 1/4" = 1'-0"

**LATERAL SHEAR NOTES:**

- ( 2013 CBC, S0PWS-2008 ; SEISMIC DESIGN CATEGORY D & E ) FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16" O.C.
- TABLE 4.3A, AFPA S0PWS-2008
- 10. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 6" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 260 P/LF
  - 11. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 4" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 350 P/LF
  - 12. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 3" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 490 P/LF
  - 13. 3/8" WOOD STRUCTURAL PANEL WITH 84 COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 640 P/LF
  - 14. 1/2"(OR 15/32) WOOD STRUCTURAL PANEL WITH 104 COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 770 P/LF
  - 15. 1/2"(OR 15/32) STRUCT. I WOOD PANEL WITH 104 COMMON NAILS AT 2" O.C. AT EDGES AND 12" O.C. AT FIELD ..... 870 P/LF
- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 24" O.C.
- 20. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 240 P/LF
  - 21. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 P/LF
  - 22. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 4" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 480 P/LF
  - 23. BLOCKED PLYWOOD DIAPHRAGM WITH 3/8" WOOD STRUCTURAL PANEL AND 84 COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 545 P/LF
- FRAMING MEMBERS DOUGLAS FIR-LARCH AT 16" O.C.
- 24. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 6" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 320 P/LF
  - 25. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 4" O.C. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 425 P/LF
  - 26. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 6" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 640 P/LF
  - 27. BLOCKED PLYWOOD DIAPHRAGM WITH 19/32" WOOD STRUCTURAL PANEL AND 104 COMMON NAILS AT 2" O.C. STAGG. AT BOUNDARIES, 3" O.C. AT EDGES AND 10" O.C. AT FIELD ..... 730 P/LF

- NOTES:
- A. WOOD STRUCTURAL PANEL: MATERIAL APPROVED BY APA, PFS/TECO OR PITTSBURGH TESTING LABORATORIES THESE VALUES ARE FOR DOUG-FIR LARCH OR SOUTHERN PINE, OTHER LUMBER SPECIES MAY DIFFER IN SHEAR CAPACITIES.
  - B. PROVIDE 2x BLOCKING AT HORIZONTAL WOOD STRUCTURAL PANEL JOINTS.
  - C. WHERE WOOD STRUCTURAL PANEL IS APPLIED ON BOTH FACES OF WALL AND NAIL SPACING IS LESS THAN 6" O.C. PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS OR FRAMING SHALL BE 3x OR WIDER AND NAILS STAGGERED ON EACH SIDE.
  - D. FOR SHEAR WALLS USE THE FOLLOWING:
    - 1) USE 3x MEMBER @ PANEL JOINTS & HORIZONTAL BLOCKING
    - 2) EDGE NAILING SHALL BE STAGGERED
  - E. 10d SHORT BOX NAILS MAY BE USED IN LIEU OF 8d COMMON NAILS @ SHEAR WALLS ONLY. REQUIRED PLATE WASHERS AT SHEAR WALLS TO BE 3" x 3" x 22g STEEL PLATE, UNLS. WITH SUB SCRIPT 'e' WHERE STANDARD CUT WASHERS ARE OKAY (S0PWS SECT. 4.3.6.4.3) WASHER MAY BE SLOT CUT PROVIDED A STANDARD CUT WASHER IS PROVIDED BETWEEN THE WASHER AND NUT. WASHER TO BE INSTALLED WITHIN 1/2" OF SHEATHED SIDE OF PLATE
  - G. A STANDARD CUT WASHER MAY BE USED AT ALL NON-SHEAR WALL LOCATIONS WITH ANCHOR BOLTS.
- HORIZONTAL: ALL ROOF AND FLOOR SHEATHING TO BE EXPOSURE 1 OR EXTERIOR (TABLE 2306.2.1)
- ROOF: JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL PI 32/16, WITH 84 @ 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD
- FLOOR: HORIZONTAL DIAPHRAGM VALUES FOR 3/8" WOOD STRUCTURAL PANEL MAY BE USED FOR 15/32" WOOD STRUCTURAL PANELS, UNLS.
- JOIST SPACING EQUAL TO OR LESS THAN 16" O.C. 19/32" WOOD STRUCTURAL PANEL TAG SHG, PI 32/16, w/104 @ 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.
  - JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 15/32" WOOD STRUCTURAL PANEL TAG SHG, PI 40/20, w/104 @ 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.
  - JOIST SPACING EQUAL TO OR LESS THAN 24" O.C. 23/32" WOOD STRUCTURAL PANEL TAG SHG, PI 48/24, w/104 @ 6" O.C. AT EDGES AND BOUNDARIES, 12" O.C. FIELD.
  - PANEL EDGES SHALL HAVE APPROVED TAG JOINTS OR SHALL BE SUPPORTED WITH BLOCKING NOT REQUIRED WHEN LIGHTWEIGHT CONCRETE IS PLACED OVER SUBFLOOR.

**FRAMING LEGEND:**



MARK	SPACING	MANUFACTURER	SIZE & OPTIONS
C	1-JOIST @ 12" O.C.	0	11 7/8" M/L
R	1-JOIST @ 16" O.C.	0	-
S	1-JOIST @ 18" O.C.	0	-
G	2X10 @ 12" O.C.	0	11 7/8" M/L / 360
H	2X10 @ 16" O.C.	0	-
K	2X10 @ 24" O.C.	0	-
L	2X12 @ 16" O.C.	0	-
M	2X12 @ 18" O.C.	0	11 7/8" M/L / 235
N	2X12 @ 24" O.C.	0	-
P	2X12 @ 16" O.C.	0	-
T	TRUSS @ 24" O.C.	2	1-JOIST @ 19 1/2" O.C. / 3

- M-1 INDICATES (1) 1/4" x DEPTH OF JOIST MICROLAM LVL 1.9 E
- PSL INDICATES PARALLEL PSL 2.0 E
- TSR INDICATES 1 1/2" BY DEPTH OF JOIST TIMBERSTRAND RIM
- E.N. INDICATES EDGE NAILING @ 6" O.C.
- G.T. GIRDER TRUSS
- C-TM INDICATES CONNECTION BY TRUSS MANUFACTURER
- INDICATES HEADERS AND BEAMS, REFER TO ENGINEERING CALC.
- INDICATES INTERIOR BEARING WALL
- INDICATES INTERIOR BEARING WALL
- NOTE: APPLY SHEAR PRIOR TO FRAMING OF PERPENDICULAR WALL AND/OR BOX-OUTS. (WHERE APPLICABLE)

FRAMING NOTES LEGEND	CEILING JOIST SCHEDULE			
MARK	DESCRIPTION	SIZE	SPACING	SPAN GRADE NO 2
SPN12	16d SOLE PLATE NAILING @ 12" O.C.	2x4	12" O.C.	2-1"
SPN10	16d SOLE PLATE NAILING @ 10" O.C.	2x4	12" O.C.	2-2"
SPN8	16d SOLE PLATE NAILING @ 8" O.C.	2x4	12" O.C.	2-3"
SPN6	16d SOLE PLATE NAILING @ 6" O.C.	2x4	12" O.C.	2-4"
SPN4	16d SOLE PLATE NAILING @ 4" O.C.	2x4	12" O.C.	2-5"
SPN3	16d SOLE PLATE NAILING @ 3" O.C.	2x4	12" O.C.	2-6"
SPN2	16d SOLE PLATE NAILING @ 2" O.C.	2x4	12" O.C.	2-7"
SPN1	16d SOLE PLATE NAILING @ 1" O.C.	2x4	12" O.C.	2-8"

NO.	REVISIONS


**ES/IFME, INC.**  
STRUCTURAL ENGINEERS  
SAN JUAN, CA 92176  
PHONE: 714-835-2800  
FAX: 714-835-2819  
JULY 2008 03/20/2016

**ROOF FRAMING PLAN**  
**LOT 10**


"HIGHLAND ESTATES"  
SAN MATEO COUNTY, CA.  
THE CHAMBERLAIN GROUP  
MGA

PROFESSIONAL SEAL  
C 30407  
CIVIL  
STATE OF CALIFORNIA


DRAWN  
CHECKED  
PLOT DATE  
12/01/2016  
JOB NO.  
C169  
SHEET  
**S10-4**  
SHEET: 5 OF: 7




**26 SHEAR TRANSFER**




**21 SHEAR TRANSFER**




**16 SHEAR TRANSFER**




**11 JOIST DRAG STRUT**




**6 TIE DOWN CONNECTION**




**1 EAVE TRUSS SHEAR CONNECTION**




**27 WALL @ CONC OR CMU WALL**




**22 SHEAR TRANSFER**




**17 HOUSE TO GARAGE FOOTING**




**12 INTERRUPTED DRAGS**




**7 SPECIAL SHEAR AT WINDOW OPENING**




**2 DRAG TRUSS SHEAR TRANSFER**




**28 SHEAR TRANSFER**




**23 DRAG CONNECTION**




**18 BEAM POCKET DRAG CONNECTION**




**13 DRAG TIE TO TRUSS**




**8 JOIST SHEAR CONNECTION**




**3 DRAG DETAIL**




**29 EAVE RAFTER SHEAR CONNECTION**




**24 RAFTER ON RIDGE BM**




**19 ROOF CONNECTION**




**14 POST TO POST HOLDOWN**




**9 PERPENDICULAR DRAG STRUT**




**4 DRAG CONNECTION**




**30 EXTERIOR WALL**




**25 POST TO POST HOLDOWN**




**20 ROOF TO WALL SHEAR TRANSFER**



**15 SHEAR TRANSFER**



**10 BM TO POST CONNECTION**



**5 NON-BEARING WALL CONNECTION**

REVISIONS


ESI/FME, INC.  
STRUCTURAL ENGINEERS  
1500 S. GARDEN AVENUE, SUITE 100  
SAN ANTONIO, TEXAS 78205  
PHONE: 781-835-2800  
FAX: 781-835-0819

**STRUCTURAL DETAILS**

" HIGHLAND ESTATES " SAN MATEO COUNTY, CA. THE CHAMBERLAIN GROUP MGA



DRAWN -  
CHECKED -  
PLOT DATE 12/01/2016  
JOB NO. C169  
SHEET


<p>1. WB126 at Plate Break, UNO (or C316 Strap) 2. Dbl Top Plates Typical 3. 2X Blocking on Edge • Unless Interrupted by Window</p> <p>ES1/FME DRG-002</p>	<p>1. SHEAR PANEL WHERE OCCURS (PER PLAN) 2. SLAB / FTG. 3. GRADE BEAM &amp; REBAR (PER PLAN)</p> <p>ES1/FME EB-CG</p>	<p>1. 15' SQ CONC. COL. w/ (6)-#7 VERTICAL &amp; #3 TIES AT 9' o/c 2. 8' CONC. WALL 3. HORIZ. REBAR PER 40 (302) 4. BACK FILL 5. #4 @ 16' O.C.</p> <p>ES1/FME</p>	<table border="1"> <thead> <tr> <th>HOLDOWN</th> <th>A.B. DIA.</th> <th>CAPACITY</th> <th>A</th> <th>B</th> <th>C</th> <th>D</th> <th>FOOTING</th> </tr> </thead> <tbody> <tr> <td>HDU2</td> <td>5/8"</td> <td>3075 lbs</td> <td>19"</td> <td>6"</td> <td>9.5"</td> <td>10.5"</td> <td>4x4</td> </tr> <tr> <td>HTT16/HTT4</td> <td>5/8"</td> <td>4400 lbs</td> <td>19"</td> <td>6"</td> <td>9.5"</td> <td>10.5"</td> <td>4x4</td> </tr> <tr> <td>HTT22/HTT5</td> <td>5/8"</td> <td>3610 lbs</td> <td>19"</td> <td>6"</td> <td>9.5"</td> <td>10.5"</td> <td>4x4</td> </tr> <tr> <td>HDU8</td> <td>7/8"</td> <td>4165 lbs</td> <td>19"</td> <td>6"</td> <td>9.5"</td> <td>10.5"</td> <td>4x4</td> </tr> <tr> <td>HDU8</td> <td>7/8"</td> <td>6970 lbs</td> <td>33"</td> <td>9"</td> <td>16.5"</td> <td>16.75"</td> <td>4x4, (4x4)-230 (lb)</td> </tr> <tr> <td>HDU8</td> <td>7/8"</td> <td>7830 lbs</td> <td>33"</td> <td>9"</td> <td>16.5"</td> <td>16.75"</td> <td>4x4, (4x4)-230 (lb)</td> </tr> <tr> <td>HDU11</td> <td>1"</td> <td>9535 lbs</td> <td>33"</td> <td>10"</td> <td>16.5"</td> <td>16.75"</td> <td>4x4, (4x4)-230 (lb)</td> </tr> <tr> <td>HDU14</td> <td>1"</td> <td>14310 lbs</td> <td>33"</td> <td>10"</td> <td>15"</td> <td>15"</td> <td>4x4</td> </tr> </tbody> </table> <p>• ALL BOLTS A307 FC Min = 2,500 PSI All Values are ASD</p> <p>ES1/FME 03/23/09</p>	HOLDOWN	A.B. DIA.	CAPACITY	A	B	C	D	FOOTING	HDU2	5/8"	3075 lbs	19"	6"	9.5"	10.5"	4x4	HTT16/HTT4	5/8"	4400 lbs	19"	6"	9.5"	10.5"	4x4	HTT22/HTT5	5/8"	3610 lbs	19"	6"	9.5"	10.5"	4x4	HDU8	7/8"	4165 lbs	19"	6"	9.5"	10.5"	4x4	HDU8	7/8"	6970 lbs	33"	9"	16.5"	16.75"	4x4, (4x4)-230 (lb)	HDU8	7/8"	7830 lbs	33"	9"	16.5"	16.75"	4x4, (4x4)-230 (lb)	HDU11	1"	9535 lbs	33"	10"	16.5"	16.75"	4x4, (4x4)-230 (lb)	HDU14	1"	14310 lbs	33"	10"	15"	15"	4x4	<p>ES1/FME</p>
HOLDOWN	A.B. DIA.	CAPACITY	A	B	C	D	FOOTING																																																																					
HDU2	5/8"	3075 lbs	19"	6"	9.5"	10.5"	4x4																																																																					
HTT16/HTT4	5/8"	4400 lbs	19"	6"	9.5"	10.5"	4x4																																																																					
HTT22/HTT5	5/8"	3610 lbs	19"	6"	9.5"	10.5"	4x4																																																																					
HDU8	7/8"	4165 lbs	19"	6"	9.5"	10.5"	4x4																																																																					
HDU8	7/8"	6970 lbs	33"	9"	16.5"	16.75"	4x4, (4x4)-230 (lb)																																																																					
HDU8	7/8"	7830 lbs	33"	9"	16.5"	16.75"	4x4, (4x4)-230 (lb)																																																																					
HDU11	1"	9535 lbs	33"	10"	16.5"	16.75"	4x4, (4x4)-230 (lb)																																																																					
HDU14	1"	14310 lbs	33"	10"	15"	15"	4x4																																																																					
<p>1. Fir. Sheathing 2. Solid Blk. Or Rim Joist See Plan 3. 2x Deck Joist 4. (2)16d Nails Per Blk. Or 16d @ 8' o.c. + 5. Deck Sheathing 6. Edge Nailing • U.N.O.</p> <p>ES1/FME DCK-001</p>	<p>ES1/FME BB-SSTB</p>	<p>ES1/FME BB-SSTB</p>	<p>ES1/FME HOD-002</p>	<p>ES1/FME</p>																																																																								
<p>ES1/FME DCK-006a</p>	<p>ES1/FME SHR-012f</p>	<p>ES1/FME F-4165DC/CS</p>	<p>ES1/FME</p>	<p>ES1/FME</p>																																																																								
<p>ES1/FME SHR-046c</p>	<p>ES1/FME</p>	<p>ES1/FME FDN-00197</p>	<p>ES1/FME</p>	<p>ES1/FME</p>																																																																								
<p>ES1/FME ROF-032</p>	<p>ES1/FME</p>	<p>ES1/FME FDN-005</p>	<p>ES1/FME</p>	<p>ES1/FME</p>																																																																								

NO.	REVISIONS


ES1/FME, INC.  
STRUCTURAL ENGINEERS  
1000 S. GATEWAY BLVD.  
SANTA ANA, CA 92705  
PHONE: 714-935-2800  
FAX: 714-935-0819  
JL-CE08 03/23/09

STRUCTURAL  
DETAILS  
LOT 9


"HIGHLAND ESTATES"  
SAN MATEO COUNTY, CA.  
THE CHAMBERLAIN GROUP  
MGA




DRAWN	-
CHECKED	-
PLOT DATE	12/01/2016
JOB NO.	C169
SHEET	SD2




BACK TO BACK INSTALLATION (11)



TOP CONNECTION W/ 4x FILLER (10)




RAISED FLOOR HEAD-OUT (9)




INSTALLATION ON 2x PLATE (8)


**NOTES:**  
 A) OUT OF PLANE FORCES TO BE RESISTED BY OTHER FRAMING MEMBERS PER THE BUILDING DESIGN PROFESSIONAL.  
 B) BALLOON WALL APPLICATIONS REQUIRE HIGH STRENGTH ANCHORAGE. SEE FOUNDATION PLAN AND ANCHORAGE TABLES ON SHEET HFX-1




BALLOON WALL INSTALLATION (7)



TOP PLATE CONNECTIONS (6)




INSTALLATION ON FOUNDATION (5)




INSTALLATION ON NUTS&WASHERS (4)


**NOTES:**  
 ATTACHMENTS MAY BE MADE AT SCREW HOLES PROVIDED OR WITH SELF TAPPING SCREWS (#12 AT EDGES, #10 AT FACE).



6x HEADER ABOVE-SECTION (3)



TOP CONNECTION TO HEADER (2)



INSTALLATION ON CURB (1)

HFX-SERIES 78 IN. THRU 13 FOOT

Model Number	Net Height (in)	Depth (in)	Hold Down Diameter <sup>1</sup> (in)	Top Screw Qty <sup>2</sup> (ea)	Screw Qty Available at Edges (ea) <sup>3</sup>
HFX-12,15,18,21 & 24x78	78	3-1/2	1-1/8	9" Width = 5	4
HFX-9x79.5	79-1/2			12" Width = 6	
HFX-12,15,18,21 & 24x8	92-1/4			15" Width = 8	
HFX-9x8	93-3/4			18" Width = 10	5
HFX-12,15,18,21 & 24x9	104-1/4			21" Width = 12	
HFX-12,15,18,21 & 24x10	116-1/4			24" Width = 14	
HFX-15,18,21 & 24x11	128-1/4			6	
HFX-15,18,21 & 24x12	140-1/4				
HFX-15,18,21 & 24x13	152-1/4				

BALLOON PANELS 14 FEET THRU 20 FEET

Model Number	Net Height (in)	Depth (in)	Hold Down Diameter <sup>1</sup> (in)	Top Screw Qty <sup>2</sup> (ea)	Screw Qty Available at Edges (ea) <sup>3</sup>
HFX-15,18,21 & 24x14	164-1/4	3-1/2	1-1/8	15" Width = 8	6
HFX-15,18,21 & 24x15	176-1/4			18" Width = 10	
HFX-15,18,21 & 24x16	188-1/4			21" Width = 12	
HFX-15,18,21 & 24x17	200-1/4			24" Width = 14	7
HFX-15,18,21 & 24x18	212-1/4				
HFX-15,18,21 & 24x19	224-1/4				
HFX-15,18,21 & 24x20	236-1/4			8	

- Hold down bolts connect to the Panel base with (1 ea) Hardened Round, (2 ea) Round-Flat or (2 ea) SAE Washers below (1 ea) Grade 8 Hex Nut on each rod or as specified by the Building Design Professional.
- 1/4" diameter USP-WS Series screws (or equal). Length is 3" (minimum) when attached directly to the collector and 4-1/2" (minimum) when installing a 2x filler above the Panel.
- Adjacent framing with 1/4" diameter screws is required at the edges when installing a 4X filler above or when specified by the Design Professional.



**INSTALLATION INSTRUCTIONS**

A) When installing directly on concrete, place Panel over bolts and connect with (1 ea) Hardened Round, (2 ea) Round-Flat or (2 ea) SAE Washers below (1 ea) Grade 8 or 2H Heavy Hex Nut. Secure with a deep socket (recommended) until "Snug Tight".

B) If bottom connection is not detailed on plans, confirm with Design Professional before installing on Nuts & Washers or on a Mudsill.

C) Use 1/4"x4-1/2" USP-WS Series screws (or equal) at top connections with a 2x filler. If the top of Panel is in direct contact with the collector above (top plates, header, beam, etc.) use 1/4 x 3" (minimum)

D) For installations with a 4x filler above 1/4" diameter screws are required at the Panel edges to brace for the out-of-plane hinge or when they are specified by the Design Professional.



**NOTES:**  
 1) SURFACE FINISHES, CONNECTORS AND FIXTURES ARE ATTACHED TO THE PANEL FACE WITH # 10 SELF-TAPPING SCREWS SPACED NO LESS THAN 2-1/4" OC.  
 2) ATTACHMENTS TO THE PANEL EDGES ARE MADE WITH # 12 SELF-TAPPING SCREWS.  
 3) STRUCTURAL CONNECTIONS ARE TO BE DESIGNED BY THE DESIGN PROFESSIONAL.  
 4) STRUCTURAL HARDWARE USED TO TRANSFER LOADS SHOULD NOT EXCEED 12 GAGE.

REVISIONS DATE

**HARDY FRAME**  
 SHEAR WALL SYSTEM  
 1732 PALMA DRIVE, SUITE 200, VENTURA, CA 93003  
 TELEPHONE: 800 754-3030 / www.hardyframe.com

**HFX**  
 SERIES

DATE: 1-1-2016

**HFX2**

FRAMING DETAILS - HFX PANELS

THIS DETAIL SHEET IS NOT PROPRIETARY AND IS NOT REQUIRED FOR PLAN SUBMITTAL WITH HARDY FRAME PRODUCTS